



EXISTING GROUND FLOOR RECEPTION LAYOUT
 Scale 1:50

- Infill breaches through walls with intumescent filler
- Provide 30min F.R. full height partitioning above false ceiling level
- Apply intumescent filler to junction of existing full height partitioning and soffit
- Line original ceiling with British Gypsum 15mm Fireline board, provide 30 min. hatch into existing loft hatch and fire dampers to protruding ductwork #35, #36, #42

TENDER ISSUE

T1	12.10.18	INITIAL TENDER ISSUE	JDC	TC
PL1	18.09.18	INITIAL PRELIMINARY DRAWING	JC	TC
REV	DATE	DESCRIPTION	BY	APPD

CLIENT
North East London NHS Foundation Trust

PROJECT
PROPOSED REFURBISHMENT OF STAPLEFORD HOUSE
 103 STAPLEFORD CL,
 CHELMSFORD CM2 0QX

DRAWING TITLE
ABOVE CEILING ACOUSTIC & FIRE COMPARTMENTATION REFURBISHMENT DRAWING

DATE	Sept 2018	DWG. No.	4478.102	REV.	T1
SCALE	1:50 (A1)				
DRAWN BY:	JDC	DATED	18:09:2018		
CHECKED BY:	TALC	DATED	18:09:2018		
APPROVAL BY:	-	DATED	-		

AK DESIGN PARTNERSHIP LLP
 CHARTERED BUILDING CONSULTANCY
 BUILDING SURVEYORS
 BUILDING DESIGNERS
 PROJECT MANAGERS

CEME INNOVATION CENTRE
 CEME CAMPUS
 MARSH WAY
 RAINHAM
 RM13 8EU

TEL: 020 8596 7070
 E-MAIL: office@akdesign.co.uk
 WEB SITE: www.akdesign.co.uk

EXISTING FIRST FLOOR LAYOUT INDICATING
 AREAS OF COMPARTMENTATION BREACHES
 Scale 1:50

