

Lower Level Roof Plan Scale 1:100

3m

## Notes:

- 1. This drawing is based on survey information by Global Surveys. Measured Building Survey. Dated Dec 2017. Provided by Hertfordshire Constabulary Nov 2021
- 2. Existing vertical timber trims along walls and wall paper in core to be stripped.
- 3. Infill openings above doors (all around core)
- 4. New partitions constructed off raised floors with cavity barriers below but all extend through suspended ceilings.
- 5. Refix existing timber stair edgings at all levels and replace where missing to match existing

ΚEY	
	New partitions, spec. K10/115
	New Taser room wall, spec. K10/120
	New blockwork partition
	New doors, spec. L10/L20
	New glass, spec. L10
	New sanitary, spec. N13
	New fixed furniture, spec. N10
	Additional layer of Plasterboard with
	acoustic lining above dado
<b>S</b>	Security access Control
Α	Automatic Powered Doors
D039	New Door numbers
<u>(001</u> )	Room Number
D039	Riser Hatch number
	Area of felt roofing. J31
	Area of asphalt roofing. J31/130

С	PRELIM - TENDER ISSUE	22.04.22	JP
В	DRAFT - TENDER ISSUE - indicative mansafe added	31.03.22	JP
А	DRAFT - TENDER ISSUE	01.03.22	JP
REV	DESCRIPTION	DATE	BY


## WATFORD POLICE STATION **3 GEORGE STREET** WATFORD WD18 0BX

## Proposed

Roof Plan

VGA PROJECT NUMBER 7664					
DRAWING NO WPS-VGA-GS-RF-DR-A-00 254					
DRAWN / DATE JP / FEB 22	CHECKED / DATE AR / FEB 22	<sub>SCALE</sub> 1:100 at A1			

PRELIMINARY



21/04/2022 - 09:52:30