INSTALLED PDF DRAWING INDICATING THE GENERAL PLANT ROOM SERVICES LAYOUTS GUARANTEED. IT IS THE CONTRACTORS RESPONSIBILITY TO UNDERTAKE A DETAILED

IT IS GENERALLY INTENDED THAT THE EXISTING LTHW HEATING, CHILLED WATER & DOMESTIC HOT WATER SERVICES PLANT AND **EQUIPMENT WILL ALL BE REPLACED AS PART** POINTS OF CONNECTION TO THE EXISTING PIPE WORK RISERS AT THEIR ENTRY/EXIT TO

. IT IS GENERALLY INTENDED THAT THE EXISTING MECHANICAL VENTILATION PLANT AND EQUIPMENT WILL ALL BE RETAINED AS PART OF THE CONTRACT WORKS FROM THE POINTS OF CONNECTION TO THE EXISTING DUCTWORK RISERS AT THEIR ENTRY/EXIT TO EXCEPTION OF THE REPLACEMENT OF INDIVIDUAL COMPONENTS WITHIN AIR HANDLING UNITS INCLUDING FILTERS, FANS,

EXISTING DOMESTIC COLD WATER PLANT AND EQUIPMENT WILL ALL BE RETAINED AS PART OF THE CONTRACT WORKS WITH THE **EXCEPTION OF MINOR MODIFICATION TO THE** GENERALLY INTENDED THAT THE EXISTING BMS/MCC/CONTROLS EQUIPMENT AND INSTALLATION WILL ALL BE REPLACED AS PART OF THE CONTRACT WORKS TO SUIT THE NEW EQUIPMENT AND PLANT ROOM

. GENERALLY THE LOCATION OF THE NEW PRIMARY EQUIPMENT IS TO BE SIMILAR TO THE EXISTING HOWEVER THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEVELOPING THE PLANT ROOM LAYOUT OF ALL ANCILLARY EQUIPMENT, INCLUDING VALVES, FITTINGS ETC, TO ACHIEVE THE BEST POSSIBLE LAYOUT FOR SERVICING & MAINTENANCE PURPOSES. THE CONFIGURATION AND LAYOUT OF THE PLANT & EQUIPMENT TO BE

Sheet Number WPS-ACM-00-03-DR-ME-300006

Scale: NTS@A0

Rev: T1